BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No: EE/YNK/BBMP/E-PMT/06/2017-18 Dated: 18-07-2017

APPROVED TENDER SCHEDULE –'B'

Item No: 03

Name of Work:-Engagement of Gangman and Hiring of Tractor, Tippers for cleaning and Maintenance of road side drains and other cleaning works in ward No:03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri GANESH (Ganesh Engineering Works)	
				Rate	Rate in Words
1	Exacavation and removal of silt or silt maixed with sand in slushy condition from canal bed including disposing of the same in spoil bankor on the canal embankment in layers as directed etc., complete withinitial lead up to 50m and all lifts MISR 2014-15 Page no 131 item No 51	cum	1684.80	120.00	Rupees one hundred twenty only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 134 (SR 2016-17)	cum	1684.80	60.00	Rupees sixty only
3	Providing and fixing per cast solid cement concrete keerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165 mm respectively. 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including cost of all materials, labour hire charges of machinery, loading unloading lead and lift, transportation etc., complete.	cum	300.00	302.00	Rupees three hundred two only
4	Peoviding and fixing precast RCC slabs as per approved design, specification and Direction Engineer-in-charge (BBMP Approved Data Rate)	Sqm	110.70	1300.00	Rupees one thousand three hundred only
5	Engaging on Hire Basis JCB including Driver/oerator with fuel etc complete (SR 2016-17) Page No XXXXIV 1031)	Days	19.00	6524.30	Rupees six thousand five hundred twenty four and paise thirty only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri GANESH (Ganesh Engineering Works)	
				Rate	Rate in Words
6	Engaging on Hire Basis of tractor 50HP coveyance of excavated and removal of stuff from work spot (SR 2016-17) Page No XXXXIV Code 1024)	Days	84.00	2400.00	Rupees two thousand four hundred only
7	Labour charges to Unskilled Mazdoor Heavy (Page No LII SR 2016-17 SL.NO	Days	840.00	220.00	Rupees two hundred twenty only

Ganesha

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.